BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2019-20/OW/WORK_INDENT39934

APPROVED SCHEDULE - B

EE/BTP BMP/E-PMT/22/2019-20, Date: 20.01.2020

Improvements to drains of 4th main road of Pampa Extension to 5th main road of Pampa extension in ward no 7

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of U RAMESH ( )		
				In Figures		In Words
1	2241.71	Removing and refixing stone slabs of drains and pointing in CM(1:3), with all lead and left as per directions of engineer in charge of the work.	Sqm	116.83	261898.98	Rupees One Hundred Sixteen and Eighty Three Paise Only
2	872.9	KSRRB 300-1. Earthwork excavation by manual means in rodinary soil involving an average horizontal throw upto 2 m and an average lift upto 1.5m, excavated surafce levelled and sides neatly dressed, the disposed earth to be levelled neatly after breaking clods complete as per specifications.. with all lead and left as per directions of engineer in charge of the work.	Cum	144.65	126264.99	Rupees One Hundred Forty Four and Sixty Five Paise Only
3	282.42	KSRB 4-1.3: Providing and laying in position plain cement concrete of nominal mix 1:4:8 using 40mm and down size graded granite metal machine mixed, conrete laid in layers not exceeding 15 cms. Thick well compacted in foundation and plinth, including cost of all materials labour, HOM of machinery, curing complete as per specification . with all lead and left as per directions of engineer in charge of the work.	Cum	5691.37	1607356.72	Rupees Five Thousand Six Hundred Ninety One and Thirty Seven Paise Only
4	12.6	KSRB4-1.6: Providing and laying in position plain cement concrete of mix 1:2:4 with cement @ 240 kgs, with 20 mm and down size graded granite matel coarse aggregates @ 0.69 cum and fine aggragtes @ 0.459cum, machine mixed concrete laid in layers not eceeding 15 cms, thick well compacted, in foundation, plinth and cills including cost of all materials, labour HOM machinery curing complate as per specifications. with all lead and left as per directions of engineer in charge of the work.	Cum	5404.30	68094.18	Rupees Five Thousand Four Hundred Four and Thirty Paise Only
5	64.8	KSRB 5.3-1:Providing and constructing granite /trap/basalt size stone masonry in foundation with cement mortar 1:6, stone hammered dressed in courses not less than 20cms hign, bond stones at two m apart in each course including cost of materials, labour, curing etc., complete as per specifications.with all lead and left as per directions of engineer in charge of the work.	Cum	5113.89	331380.07	Rupees Five Thousand One Hundred Thirteen and Eighty Nine Paise Only
6	108	KSRB 15.1.4: Providing ruled pointing to coursed stone masonry with cement mortar 1:4, 20 mm deep, after raking joints to depth of 20mm nicely lining, including cost of materials, labour, curing complete as per specifications cement mortar 1:4. with all lead and left as per directions of engineer in charge of the work.	Sqm	155.78	16824.24	Rupees One Hundred Fifty Five and Seventy Eight Paise Only
7	180	Providing and fixing 20 cm thick pre cast RCC covering slab using reinforced cement concrete M 20 mix with stone aggregate 20 mm and down size including centring shuttering reinforcement and bar bending machine mixed concrete laid in layers not exceeding 15 cm thick wellcompacted cost of all materials labour curing comlete as per specification with all lead and left as per directions of engineer in charge of the work.	Sqm	5687.27	1023708.60	Rupees Five Thousand Six Hundred Eighty Seven and Twenty Seven Paise Only
8	1218.24	Providing granite slabs of selected quality roughly dressed and fixed in cement mortar (1:6) including fixing curing etc., complete.7.5 cm thick with all lead and left as per directions of engineer in charge of the work.	Sqm	778.88	948862.77	Rupees Seven Hundred Seventy Eight and Eighty Eight Paise Only

Signature of the contractor

16/03

Executive Engineer

	Approved Qty.	Description	Unit	Approved Tender Rates of U RAMESH ( )		
				In Figures		In Words
9	210.6	KSRB 5-14.1 : Providing and constructing load bearing wall with solid concrete blocks of size 400x100x200 mm having block density not lessthan 1800 kg/m3 and having a minimum average compressive strength 4.00 N/mm2 confirming to IS 2185 (Part) : 2005 and constructed with CM 1:4 , as per IS 2572:2005 including cost of all materials, labour charegs, scaffolding, curing complete as per specifications. KBS No.5.4 with all lead and lift , loading and unloading and allother incidental charges etc., complete as per specification and direction of the engineer-in-charge of the work.with all lead and left as per directions of engineer in charge of the work.	Sqm	902.39	190043.33	Rupees Nine Hundred Two and Thirty Nine Paise Only
10	421.04	Providing granite slabs of selected quality roughly dressed and fixed in cement mortar (1:6) including fixing curing etc., complete10cms thick.with all lead and left as per directions of engineer in charge of the work.	Sqm	1014.77	427258.76	Rupees One Thousand Fourteen and Seventy Seven Paise Only
11	1579.5	KSRB 5-8.1: Providing one line dressing to granite stone slabs/granite stone masonry as per specifications. with all lead and left as per directions of engineer in charge of the work.	Sqm	998.08	1576467.36	Rupees Nine Hundred Ninety Eight and Eight Paise Only
12	4680	Providing and fixing Pre cast solid concrete kerb stones made out of CC 1:2:4 of size 450x150x500 mm and finished with CM 1:3 plastering and finishing cutting etc., complete.with all lead and left as per directions of engineer in charge of the work.	Nos	490.69	2296429.20	Rupees Four Hundred Ninety and Sixty Nine Paise Only
13	2106	KSRB 5-9.1:Providing and applying ready mix priming coat over ocncrete / masonry, / asbestos cement sheet / plastered surfaces includding preparing the surface after thorougly cleaning of oil, grease, dirt and other foreign matter and sand papering including cost of materials, labour compelte as per specifications. with all lead and left as per directions of engineer in charge of the work.	Sqm	41.17	86704.02	Rupees Forty One and Seventeen Paise Only
14	410	Providing and fixing MS Grating 260x260 mm with all lead and left as per directions of engineer in charge of the work.	Nos	88.96	36473.60	Rupees Eighty Eight and Ninety Six Paise Only
15	872.9	KSRRB M100-1 Loading and unloading of stone boulder/stone aggregates/ sand/ kanker/ moorum. KSRRB M100-1:Placing tipper at loading point loading with front end loading, dumping turning for return trip, excluding time for haulage and return trip complete as per specification MORTH Chapter 1 with all lead and left as per directions of engineer in charge of the work.	Cum	99.03	86443.29	Rupees Ninety Nine and Three Paise Only
16	42	KSRRB M2900-2.1. Laying Reinforced cement concrete pipe NP2 / prestressed concrete pipe for culverts on first class bedding of granular material in single row including fixing collar with cement mortar 1:2 but excluding excavation, protection works, backfilling, concrete and masonry works in head walls and parapets complete as per specifications. MORTH Specification No. 2900 B. 1200 mm dia MORTH Specification No. 1000,2300 with all lead and left as per directions of engineer in charge of the work.	Mtr	6273.30	263478.60	Rupees Six Thousand Two Hundred Seventy Three and Thirty Paise Only
17	3.56	Providing 100mm and down size nominal size. with all lead and left as per directions of engineer in charge of the work.	Cum	1036.70	3690.65	Rupees One Thousand Thirty Six and Seventy Paise Only
18	1.58	Providing 40mm and down size nominal size with all lead and left as per directions of engineer in charge of the work.	Cum	1145.67	1810.16	Rupees One Thousand One Hundred Forty Five and Sixty Seven Paise Only
19	1.58	Providing 20mm and down size nominal size with all lead and left as per directions of engineer in charge of the work.	Cum	1145.67	1810.16	Rupees One Thousand One Hundred Forty Five and Sixty Seven Paise Only

U Ramesh

Signature of the contractor

16/03

Executive Engineer

16/03

	Approved Qty.	Description	Unit	Approved Tender Rates of U RAMESH ( )		
				In Figures		In Words
20	1.19	Providing Fine aggrgate 2.36mm nominal size with all lead and left as per directions of engineer in charge of the work.	Cum	1106.69	1316.96	Rupees One Thousand One Hundred Six and Sixty Nine Paise Only
21	25	Providing and fixing MS Grating 260x260 mm with all lead and left as per directions of engineer in charge of the work.	Nos	94.31	2357.75	Rupees Ninety Four and Thirty One Paise Only

U Ramesh
Signature of the Contractor

16/03
Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92

16/03